

Quotation

Ref. QS-20260425-4910 · Issued by Emerson EIMS Services

To (Client)	Mr. & Mrs. Wanjiku
From (Company)	Emerson EIMS Services
Quotation No.	QS-20260425-4910
Validity	30 days from date of issue
Issue Date	25 April 2026
Currency	KES — Kenyan Shilling

Project Description

Type	Residential
Location	Karen, Nairobi
Country	Kenya
Total Area	280.0 m²
Stories	2
Units	1
Bedrooms / Unit	4

GRAND TOTAL

KES 18,796,072

USD 122,174 · KES 67,129/m²

1. Scope of Work

- Site clearing and preparation
- Foundation and substructure works
- Superstructure: 2-storey residential building (280m²)
- Roofing and waterproofing
- Electrical installation and wiring
- Plumbing, drainage and water supply
- Internal and external finishes
- Painting and decorating
- External works: paving, landscaping, fencing
- HVAC and mechanical systems
- Testing, commissioning and handover

2. Itemised Bill of Quantities

A. SUBSTRUCTURE & SUPERSTRUCTURE

Item	Description	Unit	Qty	Rate (KES)	Amount (KES)
1	Portland Cement (50kg)	bag	1,265.25	953.85	1,206,859
2	Reinforcement Steel Y12 (12mm)	kg	7,026.17	130.77	918,812
3	Reinforcement Steel Y16 (16mm)	kg	6,147.90	135.38	832,303
4	Reinforcement Steel Y10 (10mm)	kg	4,391.36	127.69	560,733
5	Binding Wire (gauge 18)	kg	271.22	200.00	54,244
6	BRC Mesh A142 (4.8m×2.4m)	sheet	14.70	4,307.69	63,323
7	Fine River Sand	m³	85.25	3,230.77	275,423
8	Coarse Aggregate (20mm)	m³	170.50	4,000.00	682,000
9	Concrete Blocks 200mm (8")	piece	3,312.75	53.85	178,392
10	Concrete Blocks 100mm (4")	piece	3,975.30	27.69	110,076
11	Formwork Plywood 18mm	sheet	184.00	2,923.08	537,847
12	Timber 50×100mm (Softwood)	m	1,408.00	353.85	498,221
13	DPC Polythene (1000 gauge)	m²	29.82	153.85	4,588
14	Hardcore / Murram	m³	30.80	2,000.00	61,600
15	Anti-termite Chemical	litre	73.50	2,123.08	156,046
16	Waterproof Membrane	m²	58.80	1,153.85	67,846
17	Precast Concrete Lintel (1200mm)	piece	13.26	1,415.38	18,768
	Subtotal				6,227,080

B. ELECTRICAL INSTALLATION

Item	Description	Unit	Qty	Rate (KES)	Amount (KES)
18	Copper Wire 2.5mm² (single core)	m	173.04	89.23	15,440

Item	Description	Unit	Qty	Rate (KES)	Amount (KES)
19	Copper Wire 1.5mm ² (single core)	m	104.03	61.54	6,402
20	PVC Conduit 20mm	m	140.70	100.00	14,070
21	Switch 1-Gang 1-Way	piece	12.12	700.00	8,484
22	Socket Outlet 13A Double	piece	12.12	1,300.00	15,756
23	LED Downlight 9W	piece	12.24	1,600.00	19,584
24	Circuit Breaker MCB 20A	piece	4.04	1,300.00	5,252
25	RCCB/ELCB 40A 30mA	piece	1.01	5,000.00	5,050
26	Distribution Board 12-Way	piece	1.01	13,000.00	13,130
27	Earth Rod (1.5m Copper)	piece	1.01	3,000.00	3,030
28	Smoke Detector	piece	6.06	3,600.00	21,816
Subtotal					128,014

C. PLUMBING & DRAINAGE

Item	Description	Unit	Qty	Rate (KES)	Amount (KES)
29	PPR Pipe 20mm (Hot/Cold)	m	39.90	230.77	9,208
30	PVC Pipe 110mm (4m)	length	6.30	1,461.54	9,208
31	PVC Pipe 50mm (4m)	length	3.15	692.31	2,181
32	Toilet (Close-Coupled)	set	2.02	10,000.00	20,200
33	Washbasin (Pedestal)	piece	2.04	6,461.54	13,182
34	Shower Mixer Valve	piece	2.02	8,653.85	17,481
35	Shower Head (Rain 200mm)	piece	2.02	6,730.77	13,596
36	Basin Mixer Tap	piece	2.02	5,769.23	11,654
37	Kitchen Sink (SS Double Bowl)	piece	1.01	12,500.00	12,625
38	Kitchen Mixer Tap	piece	1.01	7,692.31	7,769
39	Water Tank (Polyethylene 2000L)	piece	1.01	25,384.62	25,638
40	Water Heater (50L Electric)	piece	1.01	28,846.15	29,135
41	Floor Drain (SS 150mm)	piece	5.10	1,153.85	5,885
42	Inspection Chamber Cover (450mm)	piece	2.02	4,807.69	9,712
Subtotal					187,472

D. FINISHES & JOINERY

Item	Description	Unit	Qty	Rate (KES)	Amount (KES)
43	Ceramic Floor Tile 600×600mm	m ²	308.00	2,000.00	616,000
44	Ceramic Wall Tile 300×600mm	m ²	35.20	1,692.31	59,569
45	Tile Adhesive (20kg)	bag	65.10	769.23	50,077
46	Tile Grout (5kg)	bag	40.95	492.31	20,160
47	Interior Emulsion Paint (20L)	can	5.50	4,307.69	23,692
48	Exterior Weather Paint (20L)	can	3.30	5,846.15	19,292

Item	Description	Unit	Qty	Rate (KES)	Amount (KES)
49	Primer/Undercoat (20L)	can	3.30	3,384.62	11,169
50	Cement Plaster (Wall 15mm)	m ²	443.47	538.46	238,791
51	Gypsum Board Ceiling (9.5mm)	m ²	302.40	1,538.46	465,230
52	Flush Door Leaf (900×2100)	piece	7.14	4,923.08	35,151
53	Timber Door Frame (900×2100)	piece	7.14	4,000.00	28,560
54	Security Steel Door	piece	1.01	22,153.85	22,375
55	Door Lock Set (Mortise)	piece	7.07	3,323.08	23,494
56	Door Hinges (3" Stainless, pair)	pair	14.14	738.46	10,442
57	Aluminum Window Frame	m ²	8.90	6,461.54	57,508
58	Float Glass 4mm (Clear)	m ²	9.07	1,476.92	13,396
59	Putty / Wall Filler (5kg)	bag	10.50	923.08	9,692
60	Granite Countertop (25mm)	m ²	3.15	14,769.23	46,523
Subtotal					1,751,122

E. EXTERNAL WORKS & ROOFING

Item	Description	Unit	Qty	Rate (KES)	Amount (KES)
61	Roofing Sheet (Box Profile 3m)	sheet	61.95	1,846.15	114,369
62	Ridge Cap	piece	13.65	584.62	7,980
63	Guttering (PVC 100mm, 3m)	length	8.40	1,000.00	8,400
64	Downpipe (PVC 75mm, 3m)	length	4.20	738.46	3,102
65	Fascia Board (225mm Timber)	m	49.35	676.92	33,406
66	Concrete Paving Block (60mm)	m ²	44.10	2,538.46	111,946
67	Topsoil	m ³	22.05	4,230.77	93,288
68	Grass Sod / Turf	m ²	77.00	676.92	52,123
69	Perimeter Wall Block (200mm)	piece	2,484.30	61.54	152,884
70	Septic Tank (Prefab 3000L)	piece	1.01	84,615.38	85,462
71	Soakaway Pit (Precast Rings)	set	1.01	33,846.15	34,185
72	Manhole Cover (Heavy Duty)	piece	3.03	5,076.92	15,383
Subtotal					712,527

F. MECHANICAL & HVAC

Item	Description	Unit	Qty	Rate (KES)	Amount (KES)
73	Split AC Unit (12000 BTU)	set	4.04	78,076.92	315,431
74	Ceiling Fan (1200mm)	piece	6.06	7,807.69	47,315
75	Exhaust Fan (200mm)	piece	3.03	4,461.54	13,518
76	Fire Extinguisher (CO2 5kg)	piece	1.01	10,038.46	10,139
77	Water Pump (0.75kW)	piece	1.01	26,769.23	27,037
Subtotal					413,440

3. Cost Build-up

Component	Amount (KES)	USD
Material cost	KES 9,419,666	\$ 61,228
Labor cost	KES 1,304,020	\$ 8,476
Equipment cost	KES 927,303	\$ 6,027
Overhead	KES 1,031,625	\$ 6,706
Contingency	KES 1,485,423	\$ 9,655
Subtotal	KES 14,168,037	\$ 92,092
Contractor's profit	KES 2,450,949	\$ 15,931
Gross total	KES 16,618,986	\$ 108,023
Discount (2.5%)	KES 415,475	\$ 2,701
Net before VAT	KES 16,203,511	\$ 105,323
VAT (16%)	KES 2,592,562	\$ 16,852
GRAND TOTAL	KES 18,796,072	\$ 122,174
Cost per m ²	KES 67,129	\$ 436

4. Payment Schedule

Terms: 40/30/20/10

Stage	%	Amount (KES)
Foundation	40%	KES 7,518,429
Superstructure	30%	KES 5,638,822
Finishes & MEP	20%	KES 3,759,214
Handover	10%	KES 1,879,607

Estimated duration	4 months
---------------------------	----------

5. Exclusions

- Land acquisition and survey costs
- Government permit and approval fees
- Furniture, fittings and equipment (FF&E;)
- Temporary power and water supply during construction
- Professional fees (architect, engineer, QS)
- Land rates, taxes and insurance

6. Terms & Conditions

- Prices are valid for the stated validity period only
- Variations to scope will be priced separately
- Payment to be made within 14 days of each stage certificate
- Retention of 5% to be released 6 months after practical completion
- Contractor to provide 12-month defects liability period
- All works to comply with local building regulations
- Client to provide clear site access and water/power connection
- All prices shown in KES (Kenyan Shilling)

7. Acceptance

For the Contractor

Name & Signature:

Date: _____

For the Client

Name & Signature:

Date: _____