

Comprehensive Project Report

Residential Development - Karen, Nairobi

Project	Residential Development - Karen, Nairobi
Location	Karen, Nairobi
Country	Kenya
Building Code	Kenya Building Code 2020
Building Type	Residential
Total Area	280.0 m²
Stories	2
Dwelling Units	1
Bedrooms / Unit	4
Total Rooms	6
Footprint	140.0 m²
Perimeter	47.3 m
Plot Coverage	40.0%
Generated	25 April 2026, 00:11

This report consolidates the complete design, technical, and cost picture for the above project as produced by the Emerson EIMS Building Suite Pro. It is intended as a client-facing deliverable covering all 13 design phases, structural / electrical / plumbing summaries, material breakdowns, cost build-up, and required drawings. All currency values are shown in KES (with the USD equivalent for cross-border reference where applicable).

1. Site Analysis & Planning Compliance

Front setback	5m
Side setback	2m
Rear setback	3m
Minimum parking	0.5 per unit (0 total)
Access requirements	Min corridor 1.2m, stairs 0.9m

2. Structural Summary

Foundation type	Strip Foundation
Foundation depth	1.2 m
Wall system	Reinforced Concrete Block (200mm external, 100mm internal)
Slab system	Reinforced Concrete Slab (150mm)
Roof system	Pitched Roof with Box Profile Sheetting
Concrete volume	0.0 m³
Reinforcement steel	17,565 kg
Masonry blocks	9,772 pcs
Ceiling height	2.7 m

3. Building Services Summary

Electrical

Light points	12
Socket outlets	12
Distribution boards	1
Estimated load	9.0 kW

Plumbing & Drainage

Bathrooms	2
Kitchens	1
Water storage	2,000 L
Sewage system	Septic Tank with Soakaway

4. Material Cost Breakdown

Category	Line Items
Plumbing	14
External	12
Mep Hvac	5
Electrical	11
Structural	17
Finishes	18
Total line items	77
Total material (USD)	\$ 75,343
Total material (KES)	KES 11,591,286

5. Project Cost Summary

Component	Amount (KES)	Amount (USD)
Material cost	KES 11,591,286	\$ 75,343
Labor cost	KES 1,304,020	\$ 8,476
Equipment cost	KES 927,303	\$ 6,027
Overhead	KES 1,031,625	\$ 6,706
Contingency	KES 1,485,423	\$ 9,655
Contractor profit	KES 2,450,949	\$ 15,931
TOTAL PROJECT COST	KES 18,790,605	\$ 122,139
Cost per m²	KES 67,109	\$ 436

(USD shown for reference; quotations issued in KES)

6. 13-Phase Project Status

#	Phase	Status
1	Satellite Site Analysis	Pending Input
2	Geotechnical Investigation	Pending Input
3	Foundation & Structural	Pending Input
4	Floor Plans & Architecture	Pending Input
5	Electrical Systems	Pending Input
6	Plumbing & Water	Pending Input
7	Bill of Quantities	Pending Input
8	Infrastructure & Energy	Pending Input
9	Landscape Design	Pending Input
10	Permits & Compliance	Pending Input
11	3D / BIM / Drawings	Pending Input
12	Financial & ROI	Pending Input
13	Project Integration	Pending Input

7. Drawings & Deliverables

- Site Plan
- Foundation Plan
- Floor Plan (All Levels)
- Roof Plan
- Elevation Views (Front, Rear, Side)
- Cross Section
- Electrical Layout
- Plumbing Layout
- Structural Details
- Door & Window Schedule

8. Notes

- All quantities are computed from the project parameters supplied at run-time and follow standard BoQ generation rules. Verify against approved drawings before procurement.
- Material rates incorporate country-specific market data where available; client may override individual rates inside the Costing tab to match their procurement reality.
- This report is generated automatically by the Emerson EIMS Building Suite Pro. For dispute, design review or stamping use the relevant signed drawings and a registered consulting engineer.
- Contact: services@emersoneims.com · www.emersoneims.com